

REQUEST FOR PROPOSAL (RFP)

Rajasthan State Power Distribution Corporation Ltd (RSPDC)

Project: 33kV Substation Upgrade & Feeder Cable Replacement

RFP Reference: RSPDC/ELEC/2025-26/PO-4487

Date of Issue: 30 May 2025

Submission Deadline: 15 June 2025

Delivery Location: Jaipur Central Substation, Mansarovar, Rajasthan

Scope of Work

Rajasthan State Power Distribution Corporation Ltd (RSPDC) invites sealed bids from qualified cable manufacturers for the supply of power cables for the 33kV substation modernisation project. The scope of this procurement includes low-voltage internal wiring, medium-voltage feeder cables, and high-voltage underground transmission cables required for the upgrade.

Technical Specifications — Line Items

Item	Description & Specifications	Quantity	Primary Application
1	Internal Panel Wiring: 3 core, 4 sq.mm, Copper conductor, XLPE insulated, 1100V grade	2000 Meters	LT panel internal connections
2	LT Distribution Feeder: 4 core, 25 sq.mm, Copper conductor, PVC insulated, 1100V grade, SWA (Steel Wire Armoured)	3500 Meters	Underground LT distribution from transformer

Item	Description & Specifications	Quantity	Primary Application
3	MV Feeder Cable (Custom): 3 core, 120 sq.mm, Copper conductor, EPR insulated, 3300V grade, SWA armoured. Must comply with IS 7098 Part 2	1500 Meters	Medium voltage feeder from 33/11kV transformer
4	HV Underground Transmission (Custom): 1 core, 400 sq.mm, Aluminium conductor, XLPE insulated, 11000V (11kV) grade. Must comply with IEC 60502-2 and IS 7098 Part 2. Requires partial discharge testing at 2.5 U0	800 Meters	HV underground transmission from grid interconnect
5	Control & Instrumentation (Custom): 12 core, 1.5 sq.mm, Copper conductor, LSZH insulated, 600V grade, overall screened with aluminium-mylar tape. Fire-retardant per IEC 60332-3 Category C	1200 Meters	SCADA control signalling between relay panels
6	Aluminium Feeder Cable: 3 core, 240 sq.mm, Aluminium conductor, XLPE insulated, 1100V grade, SWA armoured	4000 Meters	Main LT distribution backbone

Commercial Terms

- **Payment Schedule:** 30% advance, 60% on delivery, and 10% following successful commissioning.
- **Warranty:** 5 years from the date of commissioning.
- **Liquidated Damages:** 0.5% per week of delay, capped at a maximum of 10%.
- **Delivery Timeline:** Within 8 weeks from the issuance of the purchase order.
- **Inspection:** Third-party inspection at the manufacturing facility by an RSPDC nominee.

Compliance Requirements

- All cables must strictly comply with relevant IS/IEC standards.
- Type test reports must be provided from a NABL accredited laboratory.
- The manufacturer must hold valid ISO 9001:2015 and ISO 14001 certifications.
- A valid BIS license for the relevant cable types is mandatory.

Authorized Representative: Person

Date: Date